



TDMTT-HL

- 3 × 300W solar panels
- 2x24V230AH lithium batteries with heater
- 21.3ft hydraulic mast
- Widely used in CCTV security, communication, lighting, etc.



SPECIFICATIONS

System:	DC24V
Remote Monitoring:	Victron Cerbo GX
Solar System:	Solar
No. of Solar Panel:	3
Panel Wattage:	340W
Panel Output:	900W
Panel Material:	Monocrystal Silicon
Solar Controller:	Victron SmartSolar MPPT 150/70-Tr
No. of Battery:	2 x 24V230AH lithium with heater
Capacity:	400AH, DC24V
Material	Lithium
Battery Meter:	Victron Battery Monitor BMV-712 Smart
Battery Charger:	AC110V-DC24V 40A
Inverter:	DC24V-AC110V 500W
Dimensions (in):	133.8*57.8*118
Weight (lb):	2425

TRAILER

Trailer:	Single axle, mechanical brake
Suspension System:	Leaf spring
Tire:	15"
Tow Hitch:	50mm ball hitch
Paint:	Powder coat to prevent corrosion

MAST TOWER

Type:	Hydraulic mast
Mast Height:	21.3ft
Coil Cable:	1 x CAT6 + 3 x 2.5mmsq
Camera box:	Hexagon box with 3 blue strobe lights



TDMTT-HL

MAST DOWN



MAST UP

